
COMMERCIAL SITE PLAN FOR

ADVENTURE CAMPER RENTALS, LLC.


TAX MAP 6, LOT 16, ROUTE 4, NOTTINGHAM, NH 03290 ROCKINGHAM CO.

- THE PURPOSE OF THIS PLAN IS TO SHOW A COMMERCIAL SITE PLAN ON LOT
- 2. THE PROPERTY IS DESIGNATED AS MAP 6, LOT 16.
- 3. THE AREA OF THE EXISTING LOT 16 IS 10.72 ACRES (467,063 SQFT.)
- THE CURRENT OWNER FOR LOT 16, BRETT & AMY TKACZYK, 30 MILL POND ROAD, NORTHWOOD, NH 03261

- THE EXISTING USE OF TM 6 LOT 16 IS VACANT LAND.
- 9. THE PROPOSED USE OF TM 6 LOT 16 WILL BE COMMERCIAL DEVELOPMENT.
- 10. THIS SITE PLAN FALLS UNDER THE NOTTINGHAM IMPACT FEE ORDINANCE.
- 11. SEWER TO BE PROVIDED BY ON-SITE SEPTIC SYSTEMS.
- 12. WATER TO BE PROVIDED BY ON-SITE WELLS.
- 4. ABUTTING PROPERTY INFORMATION PROVIDED BY A COMBINATION OF ON-LINE TAX MAP DATA AND DATA PROVIDED BY granitview.unh.edu.



LOCATION PLAN



VICINITY SKETCH

SHEET INDEX

<u>DWG</u>	SHT NO.	DESCRIPTION
CVR ECP PSP PGP DPP PUP PLND PLP PSLP	1 OF 14 2 OF 14 3 OF 14 4 OF 14 5 OF 14 6 OF 14 7 OF 14 8 OF 14 9 OF 14	COVER SHEET EXISTING CONDITIONS PROPOSED SITE PLAN PROPOSED GRADING PLAN PROPOSED DRIVEWAY PLAN & PROFILE PROPOSED UTILITY PLAN PROPOSED LANDSCAPING PLAN PROPOSED LIGHTING PLAN SIGHTLINE PLAN
DET-1 DET-2 DET-3 DET-4 DET-5	10 OF 14 11 OF 14 12 OF 14 13 OF 14 14 OF 14	GENERAL DETAILS DRAINAGE & UTILITY DETAILS LANDSCAPE & LIGHTING DETAILS EROSION CONTROL DETAILS EROSION CONTROL NOTES

PROFESSIONAL CONSULTANTS LIST

NEW HAMPSHIRE LAND CONSULTANTS, PLLC. 683C FIRST NH TURNPIKE (RT.4)
NORTHWOOD, NH 03261 PH:(603) 942-9220

FRAGGLE ROCK ENVIRONMENTAL, DAMON E. BURT, CWS, CPESC, 38 GARLAND ROAD, STRAFFORD, NH 03884

PH: (603) 969-5574

ENGINEER:

JEFF BURD, RJB ENGINEERING, 2 GLENDALE ROAD.





- U.S. Army Corps of Engineers 2016. National Wetland Plant List/State List, Version 3.3



INITIAL PLAN SET SUBMISSION DATE

APRIL 18, 2022

Latest revision date:






PENDING



THE LOCATION OF ANY UTILITY INFORMATION SHOWN ON THIS PLAN IS APPROXIMATE. NEW HAMPSHIRE LAND CONSULTANTS, PLLC. MAKES NO CLAIM TO THE ACCURACY OR COMPLETENESS OF UTILITIES SHOWN. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ANY UTILITIES WHETHER THEY BE ABOVE OR BELOW GROUND. PRIOR TO ANY EXCAVATION ON SITE THE CONTRACTOR SHALL CONTACT DIG SAFE AT 1—888—DIG—SAFE (1—888—344—7233).

NOTE:

ALL MATERIALS AND METHODS OF CONSTRUCTION SHALL CONFORM TO THE TOWN OF NOTTINGHAM REGULATIONS AND THE NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", LATEST EDITION.







COVER SHEET
TAX MAP 6 LOT 16 APPLICANT / OWNER:

ADVENTURE CAMPER RENTALS, LLC. **BRETT AND AMY TKACZYK** 30 MILL POND ROAD, NORTHWOOD NH 03261

PROJECT LOCATION


CVR


ROCKINGHAM CO.


DATE: APRIL 18, 2022


SHT. 1 of 14


683C FIRST NH TURNPIKE, NORTHWOOD, NH 03261 PH. 603-942-9220 WEBSITE: NHLANDCONSULTANTS.COM
























- ALL PAVEMENT, BASE MATERIALS, AND WORKMANSHIP SHALL BE IN COMPLIANCE WITH N.H.D.O.T. "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" LATEST EDITION
- ALL EMBANKMENT MATERIAL SHALL BE CLEAN WELL GRADEDMATERIAL FREE FROM ROOTS, STUMPS, LOAM AND LEDGE / ROCK HAVING D50 NO GREATER THAN 12"
- 3. PROVIDE 4" MINIMUM "TRACKED" LOAMED, SEED, AND MULCH ON ALL SLOPE GRADING, UNLESS OTHERWISE NOTED.

DRIVEWAY APRON PAVED SECTION

NOT TO SCALE



THE SUBGRADE FOR THE GEOTEXTILE FABRIC AND RIP-RAP SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS.

THE ROCK USED FOR RIP-RAP SHALL CONFORM TO THE SPECIFIED GRADATION

GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP—RAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 11 INCHES.

STONE FOR THE RIP-RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.

THE OUTLET PROTECTION SHOULD BE CHECKED AT LEAST ANNUALLY AND AFTER EVERY MAJOR STORM, IF THE RIPRAP HAS BEEN DISPLACED, UNDERMINED OR DAMAGED, IT SHOULD BE REPARED IMMEDIATELY. THE CHANNEL IMMEDIATELY BELOW THE OUTLET SHOULD BE CHECKED TO SEE THAT EROSION IS NOT OCCURRING. THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF OBSTRUCTIONS SUCH AS FALLEN TREES, DEBRIS AND SEDIMENT THAT COULD CHANGE THE FLOW PATTERNS AND/OR TAILWATER DEPTHS ON THE PIPES. REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID ADDITIONAL DAMAGE TO THE OUTLET PROTECTION APRON.

RIP-RAP OUTLET PROTECTION APRON

NOTES:

- THE INLET/OUTLET APRON SHALL BE PREPARED TO THE LINES AND GRADES SHOWN ON THE PLANS.
- THE RIP-RAP SHALL CONFORM TO THE SPECIFIED GRADATION
- ECTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP—RAP. DAMAGED AREAS IN THE FABRICS SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERTAPS REQUIRED FOR REPAIRS OR JOHNNO TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES (ALL
- RIP-RAP MAY BE PLACED BY EQUIPMENT (AS TO PREVENT SEGREGATION OF THE STONE SIZES) AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION.

MAINTENANCE:

- THE OUTLET PROTECTION SHALL BE CHECKED AT LEAST BI-ANNUALLY AND AFTER EVERY SIGNIFICANT RAIN EVENT. IF THE RIPRAP HAS BEEI DISPLACED, UNDERMINED OR DAMAGED, IT SHALL BE REPAIRED OR REPLACED IMMEDIATELY.
- THE CHANNEL IMMEDIATELY BELOW THE OUTLET SHOULD BE CHECKED TO SEE THAT EROSION IS NOT OCCURRING.
- THE DOWNSTREAM CHANNEL SHOULD BE KEPT CLEAR OF OBSTRUCTIONS SUCH AS FALLEN TREES, DEBRIS AND SEDIMENT THAT COULD CHANGE THE FLOW PATTERNS AND/OR TAILWATER DEPTHS ON THE PIPES.
- ALL REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID DAMAGE TO THE OUTLET PROTECTION APRON.

LOCATION	L	W1	W2	D	STONE SIZE D ₅₀
FES #1	11.7'	6'	12.9	5"	3"

* STONE SIZE SHOWN ON THE PLANS AS CLASS A, B, OR C STONE FILL SHALL CONFORM WITH THE REQUIREMENTS OF SECTION 585 OF THE NHDOT STANDARD SPECIFICATIONS.

FIFTY PERCENT BY WEIGHT OF THE RIPRAP MIXTURE SHALL BE SMALLER THAN THE MEDIAN SIZED STONE DESIGNATED AS 450. THE LARGEST STONE IN THE MIXTURE SHALL BE 1.5 TIMES THE 450 SIZE.

CONSTRUCTION SPECIFICATIONS:

DREDARE REDDING

BECAMBLE BEDUNGS:

BACKFILL MATERIAL AROUND THE END SECTION MAY BE THE SAME AS THE MATERIAL AROUND THE PIPE, PLACE A FEW INCHES OF BACKFILL MATERIAL IN THE TRENCH OR DITCH WHERE THE END SECTION WILL BE PLACED. COMPACT AND CONTOUR THIS BEDDING MATERIAL TO GENERALLY MATCH THE END SECTION, EXCAVATE AN AREA IN THE BEDDING WHERE TOE TROUGH WILL SEAT SO THAT THE END SECTION, WILL BE LEVEL WITH THE BOTTOM OF THE TRENCH OR DITCH IN THE TINISHED INSTALLATION.

PLACE END SECTION OF PIPE:

OPEN THE END SECTION COLLAR AND SEAT IT OVER THE TWO PIPE CONNECTIONS. ONCE THE END SECTION IS POSITIONED, CHECK TO MAKE SURE THAT THE INVERT OF THE END SECTION MATCHES THE INVERT OF THE PIPE AND THAT THE END SECTION IS LEVEL WITH THE TRENCH OR DITCH SOTTOM.

SECURE THE END SECTION:

SUP THE STANLESS STEEL ROD THROUGH THE PRE-DRILLED HOLES AT THE TOP OF THE COLLAR. THE ROD SHOULD BE BETWEEN THE CROWNS OF THE TWO PIPE CONNECTIONS. PLACE A WASHER ON EITHER END OF THE ROD. PLACE A NUT ON EITHER END OF THE ROD AND TIGHTEN WITH A WRENCH.


SECURE THE TOE TROUGH:

CORRE TO THE TOTAL THE STATE CONTROL TO THE TOTAL THE TROUGH BE SECURED WITH CONCRETE. POUR CONCRETE IN THE TROUGH UP TO THE LEVEL OF THE TRENCH OR DITCH BOTTOM AND LAUNG THE ENTIRE LENGTH OF THE TROUGH.

FINISH BACKFILL: SHOVEL BACKFILL AROUND THE END SECTION IN 6 TO 9 INCH LAYERS EQUALLY ON BOTH SIDES, KNIFING IT TO ELIMINATE VOIDS. TAMP WITH A SMALL-FACED COMPACTOR OR OTHER EQUIPMENT SUITABLE FOR SMALL AREAS. CONTINUE PLACING, KNIFING, AND COMPACTING BACKFILL LAYERS TO THE TOP OF THE END SECTION TO SEAT IT WELL INTO THE BACKFILL.


FLARED END SECTION


HIGH DENSITY POLYETHYLENE (HDPE)



	DIMENSIONS, INCHES (mm)					
PIPE DIAMETER	PART NO.	A, ±1 (25)	B MAX	H, ±1 (25)	L, ±1/2 (13)	W, ±2 (50)
12", 15" (300,375)	1210 NP	6.5 (165)	10 (254)	6.5 (165)	25 (635)	29 (736)

NOT TO SCALE





CONSTRUCTION NOTES

- THE FOUNDATION AREA OF THE WATERWAY SHALL BE CLEARED AND GRUBBED OF ALL TREES, BRUSH, STUMPS AND OTHER OBJECTIONABLE MATERIAL. MATERIALS REMOVED SHALL BE DISPOSED OF SO THEY DO NOT INTERFERE WITH THE CONSTRUCTION OF PROPER FOUNDTON OF THE WATERWAY.
- EARTH FILLS REQUIRED TO MEET SUBGRADE REQUIREMENTS BECAUSE OF OVER EXCAVATION OR TOPOGRAPHY SHALL BE COMPACTED TO THE SAME DENSITY AS THE SURROUNDING SOIL TO PREVENT UNEQUAL SETTLEMENT THAT COULD CAUSE DAMAGE TO THE COMPLETED WATERWAY. FASTH REMOVED AND NOT NEEDED IN CONSTRUCTION SHALL BE SPREAD OR DISPOSED OF SO THAT IT WILL NOT INTERFERE WITH THE FUNCTIONING OF THE WATERWAY.
- 4. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER AS TO MINIMIZE EROSION AND AIR AND WATER POLLUTION. ALL APPROPRIATE STATE AND LOCAL LAWS AND REGULATIONS SHALL BE COMPLED WITH FOR DESIGN AND INSTALLATION.
- THE WATERWAY SHALL BE STABILIZED USING THE APPROPRIATE "BEST MANAGEMENT PRACTICES" FOR VEGETATIVE MEASURES.

MAINTENANCE


MAINTENANCE OF THE VECETATION IN THE GRASSED WATERWAY IS EXTREMELY IMPORTANT IN ORDER TO PREVENT RILLING, EROSION AND FAILURE OF THE WATERWAY. MOWING SHOULD BE DONE FREQUENTLY ENDUGHT OF KEEP THE VECETATION IN VIGOROUS CONDITION AND TO CONTROL ENCROACHMENT OF WEEDS AND WOODLY VECETATION, HOWEVER IT SHOULD NOT BE MOWED TO CLOSELY AS TO REDUCE EROSION REISTANCE IN THE WATERWAY. THE WATERWAY SHOULD BE INSPECTED PERIODICALLY AND AFTER EVERY MAJOR STORK—NACE IN THE WATERWAY. RILLS AND DAMAGED AREAS SHOULD BE FROM THE PREPARED AND RELATED THE ASSESSMENT TO PREVENT PURTHER DETERIORATION. FERTILIZE ON AN "AS-NEEDED" BASIS TO KEEP THE GRASS HEALTHY.

GRASS LINED TREATMENT SWALE

LLC. 03261 GENERAL DETAILS
TAX MAP 6 LOT 16
APPLICANT / OWNER:
ADVENTURE CAMPER RENTALS, LI
BRETT AND AMY TKACZYK
30 MILL POND ROAD, NORTHWOOD NH 032
PROJECT LOCATION
TAX MAP 6 LOT 16, ROUTE 4, NOTINGHAM NH JOB NO: 592.00

叫簡

ROCKINGHAM CO. DATE: APRIL 18, 2022 DET-1 SHT. 10 of 14



DID DAD CDADATION


GRAVEL FILTER

	RIP-	-RAP G	RADATI	NC	
		% FINER BY	WEIGHT		
STONE SIZE	D 50 = 6"	D ₅₀ = 9"	D 50 = 12"	D ₅₀ = 18"	D 50 = 24"
2"	0-15%	0%	-	-	-
4"	20-35%	10-20%	0-10%	-	-
6"	35-50%	25-35%	10-25%	9-10%	-
8"	50-65%	30-50%	20-30%	10-20%	0-10%
10"	60-80%	40-60%	30-40%	15-30%	5-15%
12"	75-100%	-	-	-	-
15°	_	70-100%	45-60%	25-40%	20-30%
20"	-	-	70-100%	40-60%	30-45%
30"		_	_	70-100%	50-70%

	CIVADATION					
]	SIEVE SIZE	% PASSING BY WEIGHT				
1	3½"	100				
1	3"	85-100				
1	11/2"	60-90				
1	ት"	40-70				
1	¾° .	20-50				
1	NO. 4	10-40				
1	NO. 200	0-8				
1						
1						


RIP RAP SWALE

NOT TO SCALE



TYPICAL EMERGENCY SPILLWAY DETAIL

NOT TO SCALE



NOTES

- THE FOUNDATION AREA SHALL BE CLEARED OF TREES. LOGS, STUMPS, ROOTS, BRUSH. BOULDERS, SOO AND RUBBISH. SCANIFY SURFACE BEFORE PILACING FILL THE AREA SHALL BE MOIST FOR GOOD BONDING OF THE NEW FILL. KEEP STANDING WATER FROM FORMING ON OR NEAR THE FILL AREA.
- THE FILL SHALL BE FREE OF DETRIMENTAL AMOUNTS OF SOD, ROOTS, FROZEN SOIL, STONES LARGER THAN 6 INCHES AND OTHER OBJECTIONABLE MATERIAL. CRUSHED GRAVEL (3/4") SHALL BE PLACED AROUND PIPES AND CONCRETE STRUCTURES.
- 3. THE PLACING AND SPREADING OF FILL SHALL BE STARTED AT THE LOWEST POINT IN THE BERM AREA AND BROUGHT UP IN HORIZONTAL LAYERS (LIFTS) OF ABOUT 12" SO THAT REQUIRED COMPACTION CAN BE OBTAINED. THE DISTRIBUTION AND GRADATION OF MATERIALS SHALL BE SUCH THAT NO LENSES, POCKETS, STREAKS OR LAYERS OF MATERIAL DIFFER SUBSTANTIALLY IN TEXTURE OR GRADATION FROM THE SURROUNDING MATERIAL.
- 4. THE MOISTURE CONTENT OF THE FILL MATERIAL SHALL BE ADEQUATE FOR OBTAINING THE REQUIRED COMPACTION.
- 5. CONSTRUCTION EQUIPMENT SHALL BE OPERATED OVER AREAS OR EACH LAYER OF FILL TO INSURE REQUIRED COMPACTION. USE SPECIAL EQUIPMENT IF NECESSARY. FILL ADJACENT TO PIPES AND STRUCTURES SHALL BE COMPACTED BY HAND TAMPING OR PLATE VIBRATOR. FILL ADJACENT TO CONCRETE STRUCTURES SHALL NOT BE COMPACTED UNTIL CONCRETE HAS CURED STRONG ENOUGH TO SUPPORT THE LOAD.
- 6. FOR PROTECTION ALL EXPOSED AND DISTURBED SURFACES (OTHER THAN THE FILTER MEDIA) SHALL HAVE A COVER OF VEGETATION, PREFERABLY TOPSOIL AND SEED. FOLLOW SEEDING SPECIFICATIONS AND GENERAL NOTES IN THE EROSION CONTROL DETAILS SECTION IN THIS PLANSEY.

DETENTION BASIN DETAIL

SECTION

SAFETY

PONDS THAT ARE EASILY ACCESSIBLE IN POPULATED AREAS SHOULD INCORPORATE ALL POSSIBLE SAFETY PRECAUTIONS. DUE TO ONLY TEMPORARY WATER LEVELS IN THESE BASINS, FENCING IS NOT NECESSARY.

MAINTENANCE

- MAINTENANCE IS NECESSARY IF THE BASIN IS TO CONTINUE TO FUNCTION AS DESIGNED. THE LANDOWNER MUST BE AWARE OF THE REQUIREMENTS FOR A PROPERLY OPERATIONAL BASIN AND A PLAN BE DEVELOPED FOR REQUILAR SCHEDULED MAINTENANCE.
- THE EMBANKMENT SHOULD BE INSPECTED TO DETERMINE IF RODENT BURROWS, WET AREAS OR EROSION OF THE FILL IS TAKING PLACE.
- PIPE INLETS AND SPILLWAY STRUCTURES SHOULD BE INSPECTED ANNUALLY AND AFTER EVERY MAJOR STORM. ACCUMULATED DERRIS AND SEDMENT SHOULD BE REMOVED. IF PIPES ARE COATED, THE COATING SHOULD BE CHECKED AND REPAIRED AS NECESSARY.
- PIPE OUTLETS SHOULD BE INSPECTED ANNUALLY AND AFTER EVERY MAJOR STORM. THE CONDITION OF THE PIPES SHOULD BE NOTED AND REPAIRS MADE AS NECESSARY. IF EROSION IS TAKING PLACE, THEN MEASURES SHOULD BE TAKEN TO STABILIZE AND PROTECT THE AFFECTED AREA OF THE OUTLET.

ELEV. = 262.50' ELEV. TOP OF IMPERVIOUS CORE 1' BELOW TOP

3'-0"

-SEEP COL

6'-0"

IMPERVIOUS CORE AND SOIL

IMPERVIOUS CORE AND POND LINER SOIL SAMPLES
AND SIEVE ANALYSIS TO BE SUBMITTED FOR APPROVAL PRIOR TO CONSTRUCTION,
IMPERVIOUS SOILS TO MEET THE FOLLOWING CRITERIA,
SOIL SHALL HAVE NO ORGANIC MATTER OR FROZEN MATERIAL AND NO STONES
LARGER THAN 2/3 OF THE MAXIMUM LIFT SIDE. STONES AROUND ANY STRUCTURES AND/OR
CONDUITS SHALL NOT EXCEED 3 INCHES. FILL MATERIAL SHALL HAVE THE FOLLOWING GRADATION:

3. IMPERVIOUS SOIL SHALL BE INSTALLED WITHIN THE LIMITS SHOWN ALONG THE BERM AREA.
THE SOIL SHALL BE KEYED 12" INTO THE BOTTOM OF THE POND AND SHALL BE PLACED IN
LIFTS NOT EXCEEDING 9" AND COMPACTED TO A MINIMUM 95% OF THE WET WEIGHT AS DETERMINED
BY MODIFIED TESTING (ASTM 1557)

IMPERVIOUS CORE TO BE
THE WIDTH OF TRENCH PLUS KEYED INTO SIDES

KEY IN 2' MIN

SEDIMENT SHOULD BE CONTINUALLY CHECKED IN THE BASIN. WHEN SEDIMENT ACCUMULATIONS REACHED THE PREDETERMINED DESIGN ELEVATION, THEN THE SEDIMENT SHOULD BE REMOVED AND PROPERLY DISPOSED OF.

NOT TO SCALE

z 0

NO SCALE

N.H. LAND Consultants SURVEYING-LAND PLANNING-REAL ESTATE

411

LC.

DRAINAGE & UTILITY DETAILS
TAX MAP 6 LOT 16
APPLICANT / OWNER:
ADVENTURE CAMPER RENTALS, LI
BRETT AND AMY TKACZYK
30 MILL POND ROAD, NORTHWOOD NH 032
TAX MAP 8 LOT 16, ROUTE 4, NOTHWAMAN NH

JOB NO: 592.00 ROCKINGHAM CO. DATE: APRIL 18, 2022

> DET-2 SHT. 11 of 14

GRADATION: Sediment Berm OUTLET % FINER BY WEIGHT STRUCTURE STONE SIZE D_m = 4" 1.0" 0-15% 15-30% 3.0" 30-50% 50-90% 100% 12" HDPE BOTTOM SEDIMENT BERM OUTLET PIPE 6" - 3/4 CRUSHED STONE BEDDING PLAN 24" x 24" GRATE EL. 261.00 OUTLET STRUCTURE 1 DETAIL GALVANIZED STEEL TRASP RACK 2" OPENINGS INFILTRATION BASIN
PLEASE ADD THE FOLLOWING NOTES TO YOUR PLANS:

- DO NOT DISCHARGE SEDIMENT-LADEN WATERS FROM CONSTRUCTION
ACTIVITIES (RUNOFF, WATER FROM EXCAVATIONS) TO THE INFILTRATION BASIN. 7" ORIFACE -AFTER THE BASIN IS EXCAVATED TO THE FINAL DESIGN ELEVATION, THE FLOOR SHOULD BE DEEPLY TILLED WITH A ROTARY TILLER OR DISC HARROW TO RESTORE INFILTRATION RATES, FOLLOWED BY A PASS WITH A LEVELING DRAG. STAINLESS STEEL ELEVATION -VEGETATION SHOULD BE ESTABLISHED IMMEDIATELY. CLIP & 3/8" DIA. CONCRETE ANCHOR -DO not place infiltration systems into service until the contributing areas have been fully stabilized. (TYP. 6 PLACES)

OUTLET STRUCTURE


OUTLET STRUCTURE


4. AT THE IMPERVIOUS DAM AREA, THE DAM SHALL BE KEYED INTO TO BOTTOM AND SIDES OF THE TRENCH A MINIMUM OF 2.* THE IMPERVOUIS SOIL SHALL BE PLACED IN IJETS NOT EXCEDING 9 AND COMPACTED TO A MINIMUM 95% OF THE WET WEIGHT AS DETERMINED BY MODIFIED TESTING (ASTM 1557)

NOTES:

SIEVE SIZE:


NOT TO SCALE





D = DIMENSION OF PLANT SPACING (SHRUB OR GROUNDCOVER AS INDICATED ON PLANS)

12" LOAM BACKFILL (CONTINUOUS THROUGHOUT AREA)




TYPICAL PERENNIAL DETAIL

NOT TO SCALE

SHRUB TO BE SET PLUMB, -TRUNK FLARE AND TOP OF ROOTBALL SHOULD BE AT GRADE (TRUNK FLARE IS WHERE THE ROOTS BEGIN TO BRANCH FROM THE TRUNK)

3" SHREDDED BARK MULCH, PULL MULCH BACK 4" FROM TRUNK

REMOVE STRING AND BURLAP FROM ROOTBALL CUT AND REMOVE WIRE BASKETS, REMOVE CONTAINERIZED PLANTS FROM THEIR CONTAINERS. TAMP BACKFILL SOIL AROUND ROOTBALL FIRMLY, TO MINIMIZE ROOTBALL SHIFT.



NOTE:


1. DO NO HEAVILY PRUNE SHRUB AT PLANTING, PRUNE ONLY CROSSOVER LIMBS AND DAMAGED OR DEAD BRANCHES.


2. BACKFILL WITH LOAM, AMEND AS REQUIRED BY LANDSCAPE ARCHITECT.


3. SHRUBS & GROUNDCOVER PLANTED ADJACENT TO CITY SIDEWALKS NEED TO BE PLACED SO THE PLANTS, AT THEIR MATURE HEIGHT &


TYPICAL SHRUB PLANTING DETAIL


NO SCALE
































LANDSCAPING AND LIGHTING DETAILS
TAX MAP 6 LOT 16
APPLICANT / OWNER:
APVENTURE CAMPER RENTALS, LLC.
BRETT AND AMY TKACZYK
30 MILL POND ROAD, NORTHWOOD NH 03281 LLC. JOB NO: 592.00

> DATE: APRIL 18, 2022 DET-3 SHT. 12 of 14

ROCKINGHAM CO.




NOTE

- 1. CONSTRUCT THE LEVEL SPREADER LIP ON A ZERO PERCENT GRADE TO INSURE UNIFORM SPREADING OF RUNOFF.
- 2. LEVEL SPREADER SHALL BE CONSTRUCTED ON UNDISTURBED SOIL, NOT ON FILL.
- 3. THE FLOW FROM THE LEVEL SPREADER SHALL OUTLET ONTO STABILIZED AREAS. WATER SHOULD NOT BE ALLOWED TO RE-CONCENTRATE BELOW THE SPREADER.
- 4. PERIODIC INSPECTION AND REQUIRED MAINTENANCE SHALL BE PERFORMED.
- 5. LEVEL SPREADER TO BE 5' LONG UNLESS OTHERWISE LABELED ON THE PLAN.


THE LEVEL SPREADER SHOULD BE CHECKED PERIODICALLY AND AFTER EVERY MAJOR STORM TO DETERMINE IF THE LIP HAS BEEN DAMAGED AND TO DETERMINE THAT THE MAJOR DESIGN CONDITIONS HAVE NOT CHANGED. ANY DETRIBUENTAL SEDIMENT ACCUMULATION SHOULD BE REMOVED. IF RILLING HAS TAKEN PLACE ON THE LIP, THEN THE DAMAGE SHOULD BE REPAIRED AND RE-VEGETATED. THE VEGETATION SHOULD BE MOWED ON OCCASION TO CONTROL WEEDS AND THE ENCROACHMENT OF WOODY VEGETATION. CLIPPINGS SHOULD BE REMOVED AND DISPOSED OF OUTSIDE THE SPREADER AREA AND AWAY FROM THE OUTLET FARE. FERTILIZATION SHOULD BE DONE AS NECESSARY TO KEEP THE VEGETATION HEALTHY AND DENSE.

LEVEL SPREADER

NOT TO SCALE




SLOPE RIP-RAP DETAIL @ DRAINAGE SWALE



- SILT FENCES ARE TO BE INSPECTED IMMEDIATELY AFTER EVERY RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE IMMEDIATELY.
- SEDIMENT DEPÓSITS SHOULD BE INSPECTED AFTER EVERY STORM EVENT. THE BE REMOVED WHEN THEY REACH APPROXIMATELY ONE HALF OF THE BARRIER.
- 4. SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE FABRIC HAS BEEN REMOVED, SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND VEGETATED

SILT FENCE DETAIL





- 1. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED, NOTE: WHEN LESING CELL-O-SEED DO NOT SEED PREPARED AREA. CELL-O-SEED MIST BE INSTALLED WITH PAPER SIDE DOWN.

 BEGIN AT THE ETOP OF THE SLOPE BY ANDCORNEN THE BLANKET IN A 6" (15em) DEED X 6" (15em) NOTE THE SLOPE OF MACHORING THE BLANKET IN A 6" (15em) DEED X 6" (15em) NOTE THE TREACH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30em) APART IN THE BIOTOM OF THE TREACH. ANCHOR THE BLANKET IN A 6" STAPLES/STAKES STAPLES APPROXIMATELY 12" (30em) APART IN ATTER BOTTOM OF THE TREACH. ANCHOR THE BLANKET OF BLANKET DEED SOIL SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES STACED APPROXIMATELY 12" (30em) APART ACROSS THE WIDTH OF THE BLANKET OWN COMPACTED SOIL WITH A ROW OF STAPLES/STAKES STACED APPROXIMATELY 12" (30em) APART ACROSS THE WIDTH OF THE BLANKET OWN FOR ADMINISTRATE SOIL BLANKET OWN FOR ADMINISTRATE SOIL SECURELY FACTORING BLANKET SHE THAT CONTROL OF THE SOIL SUPPRACE STATES STAKES STA

- S. CONSECUTIVE BLANKERS SPICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STILL) WITH AN APPROXIMATE 3" (7.5cm) OVERALP, STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30cm) APART ACROSS ENTIRE BLANKET WITH.

NOTE: "IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15cm) MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.

14649 HIGHWAY 41 NORTH, EVANSVILLE, INDIANA 47725
NOTE: CANADA 1-800-772-2040 CANADA 1-800-448-2040
WWW.norgreen.com
FOR 2:1 SLOPES OVER 20' HIGH USE TEMPORAFY ELAINKET 5150
FOR 2:1 SLOPES LESS THAN 20' HIGH USE TEMPORAFY ELAINKET 575

SLOPE INSTALLATION

FOR EROSION CONTROL

NOT TO SCALE



NO SCALE



LLC.

EROSION CONTROL DETAILS
TAX MAP 6 LOT 16
APPLICANT / OWNER:
ADVENTURE CAMPER RENTALS, LL
BRETT AND AMY TKACZYK
30 MILL POND ROAD, NORTHWOOD NH 0322

JOB NO: 592.00 ROCKINGHAM CO. DATE: APRIL 18, 2022

DET-4 SHT. 13 of 14

GENERAL NOTES:

- PROJECT ENGINEER: RJB ENGINEERING, LLC., 2 GLENNDALE ROAD, CONCORD, NH 03301.
 PROJECT SURVEYOR: NEW HAMPSHIRE LAND CONSULTANTS PLLC., 683C FIRST NH TURNPIKE (RT.4), NORTHWOOD, NH 03261
 PROJECT WETLAND SCIENTIST: DAMON E. BURT, CERTIFIED WETLAND SCIENTIST #163, FRAGGLE ROCK ENVIRONMENTAL.,
 3B GARLAND ROAD, STRAFFORD, NH 03884
- ALL MATERIALS AND METHODS OF CONSTRUCTION SHALL CONFORM TO TOWN REGULATIONS AND THE LATEST EDITION OF NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION'S STANDARD SPECIFICATIONS FOR ROAD & BRIDGE CONSTRUCTION.
- IF, DURING CONSTRUCTION IT BECOMES APPARENT THAT DEFICIENCIES EXIST IN THE APPROVED DESIGN DRAWINGS, THE CONTRACTOR, DEVELOPER OR OWNER ARE RESPONSIBLE TO DOCUMENT THE APPARENT DEFICIENCIES AND NOTIFY THE DESIGN REGINEER, PRIOR TO CONTRINUING CONSTRUCTION ACTIVITIES. THE DESIGN ENGINEER, IN COOPERATION WITH THE CONTRACTOR, DEVELOPER OR OWNER WILL RESOLVE THE APPARENT DEFICIENCIES TO MEET APPLICABLE TOWN REGULATIONS.
- THE CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES PRIOR TO CONSTRUCTION TO VERIFY THE LOCATION OF ALL UTILITIES OVERHEAD OR UNDERGROUND, WITHIN THE CONSTRUCTION AREA. THE PROTECTION OR RELOCATION OF UTILITIES IS ULTIMATELY THE RESPONSIBILITY OF THE CONTRACTOR. (DIG SAFE NUMBER PROVIDED ON SHEET 1)
- 6. THE CONTRACTOR SHALL MAINTAIN EMERGENCY ACCESS TO ALL AREAS AT ALL TIMES.
- 7. NO EXCAVATED AREA SHALL BE LEFT UNATTENDED AND SHALL BE THOROUGHLY SECURED ON A DAILY BASIS.

CONSTRUCTION SEQUENCE:

- 2. CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE AS SHOWN AND DETAILED IN THIS PLAN SET.
- 3. CONSTRUCT TEMPORARY AND PERMANENT EROSION CONTROL FACILITIES (DETENTION BASIN, DIVERSION BERM, GRASS SWALE) PRIOR TO ANY EARTH MOVING OPERATION.
- 4. ALL SWALES AND DITCH LINES SHALL BE PROTECTED FROM EROSION. ALL DITCHES AND SWALES SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
- 5. PONDS AND SWALES SHALL BE INSTALLED EARLY ON IN THE CONSTRUCTION SEQUENCE (BEFORE ROUGH GRADING THE SITE).
- ALL STORM DRAINAGE SYSTEMS SUCH AS DETENTION/RETENTION BASINS, TREATMENT SWALES AND LEVEL SPREADERS SHALL BE PROTECTED FROM EROSION. ALL STORM DRAINAGE SYSTEMS SHALL BE STABILIZED PRIOR TO DIRECTING FLOW INTO THEM.
- 7. NO CATCH BASIN FRAME AND GRATE SHALL BE INSTALLED PRIOR TO PAVING (IF APPLICABLE). ALL DRAINAGE STRUCTURES ARE TO BE "PLATED" AND CUIT OUT FOLLOWING PAVING OPERATIONS, ONLY IF ALL DOWNSTREAM DRAINAGE ELEMENTS ARE STABLE, INCLUDING, BUT NOT LIMITED TO OUTLET PROTECTION, ALL SLOPE GRADING, VEGETATED OR RIPRAP SWALES, DETENTION BASIN AND TREATMENT SWALES.
- 8. IF FRAME AND GRATES ARE INSTALLED, SPECIFIC SOIL EROSION MEASURES MUST BE INSTALLED SUCH AS GRAVEL AND WIRE MESH DROP INLET SEDIMENT FILTER.
- 9. CONSTRUCT TEMPORARY CULVERTS, DIVERSION DITCHES/SWALES OR BERMS AS REQUIRED TO MINIMIZE THE EROSIVE AFFECTS OF STORMWATER RUNOFF DURING ALL CONSTRUCTION ACTIVITIES. TEMPORARY WATER DIVERSION (SWALES, BASINS, ETC.) MUST BE USED AS NECESSARY UNTIL AFEAS STABILIZED.
- 10. COMPLETE GRUBBING OPERATIONS, ALL STUMPS AND DEBRIS SHALL BE PROPERLY DISPOSED OF, PREFERABLY OFF SITE.
- 11. ALL MATERIAL SUITABLE FOR USE AS TOPSOIL SHALL BE STOCKPILED IN UPLANDS AREAS. ALL STOCKPILES SHALL BE SEEDED WITH WINTER RYE AND IF NECESSARY, SURROUNDED WITH SILT FENCE, AND/OR STRAW BALES, IN ORDER TO PREVENT OR CONTAIN SOIL EROSION.
- 12. ALL MATERIAL SUITABLE FOR FILL OR SELECT MATERIAL SHALL BE STOCKPILED IN UPLANDS AREAS, ALL STOCKPILES SHALL BE SURROUNDED WITH SILT FENCE, AND/OR STRAW BALES, IN ORDER TO CONTAIN SOIL EROSION.
- 13. REMOVE ALL IMPROPER ROADWAY/SITE FOUNDATION MATERIAL WITHIN 18" OF SUBGRADE. REPLACE WITH COMPACTED GRANULA' FILL ACCEPTABLE TO THE STATE/TOWN SPECIFICATIONS. ALL SUITABLE FILL MATERIAL SHALL BE COMPACTED TO AT LEAST 95% OF THE DRY WEIGHT AS DETERMINED BY MODIFIED PROCTOR TESTING (ASTM. D-1356) REQUIREMENTS.
- 14. CONSTRUCT ALL UNDERGROUND UTILITIES INCLUDING, BUT NOT LIMITED TO DRAIN, DATA, CABLE AND POWER.
- 15. ROUGH GRADE SITE WITHIN LIMIT OF WORK AND COMMENCE CONSTRUCTION OF ROADWAY
- 16. SITE SHALL BE STABILIZED WITHIN 72 HOURS OF FINISHED GRADE.
- 17. COMPLETE ROADWAY SLOPE GRADING/EMBANKMENT CONSTRUCTION. ALL SLOPES SHALL BE STABILIZED AND SEEDED IMMEL AFTER GRADING. THE CONTRACTOR SHALL STABILIZES LOPES WITH APPROPRIATE SEEDING PROGRAM OR JUTE WAT, WHEREVER SPECIFIED. ALL CUT AND FILL SLOPES SHALL BE SEEDED/LOAMED WITHIN 72 HOURS OF ACHIEVING FINISH GRADE.
- 18. APPLY TOPSOIL TO SITE SLOPES AND OTHER AREAS DISTURBED BY CONSTRUCTION. TOPSOIL USED MAY BE NATIVE ORGANIC MATERIAL SCREENED AS TO BE FREE FROM ROOTS, BRANCHES, STONES, AND OTHER DELETERIOUS MATERIALS. TOPSOIL SHALL SAPPLIED SO AS TO PROVIDE A MINIMUM OF A 4-INCH COMPACTED THICKNESS. UPON COMPLETION OF TOPSOILING, FINISHED SECTIONS ARE TO BE LIMED, SEEDED, AND MULCHED. THE CONTRACTOR SHALL INSPECT COMPLETED SECTIONS OF WORK ON A REGULAR BASIS AND REMEDY ANY PROBLEM AREAS UNTIL A HEALTHY STAND OF GRASS IS ESTABLISHED.
- 19. PERFORM FINAL PAVING OPERATIONS (IF APPLICABLE), INSTALL GUARDRAIL (IF APPLICABLE) AS SHOWN ON THE APPROVED PLANS 20. MAINTAIN, REPAIR, AND REPLACE TEMPORARY EROSION CONTROL MEASURES AS NECESSARY FOR A MINIMUM PERIOD OF 12 MONTHS FOLLOWING SUBSTANTIAL COMPLETION.
- 21. AFTER STABILIZATION (12 MONTHLY FOLLOWING SUBSTANTIAL COMPLETION), REMOVE AND PROPERLY DISPOSE OF TEMPORARY EROSION CONTROL MEASURES, PREFERABLY OFF SITE.
- 22. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT IN NO CASE SHALL EXCEED 5 ACRES AT ANY ONE TIME BEFORE DISTURBED AREAS ARE STABILIZED.
- DEFINITION OF THE WORD STABLE: AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURE!
- A: BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED.
- B: A MINIMUM OF 85 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED.
- C: A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED.
- 23. ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE

WINTER CONSTRUCTION NOTES

- A.. ALL PROPOSED VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN \$:1, AND SEEDING AND PLACING \$ 10 4 TONS OF MULCH PER AGRE, SECURED WITH ANOHORED NETTING, ELSEWHERE, THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS.
- C. AFTER NOVEMBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER NHDOT ITEM 304.3.

SEEDING SPECIFICATIONS

MIXTURE	POUNDS/ACRE	POUNDS/1,000
TALL FESCUE	20	0.45
REEPING RED FESCUE	20	0.45
BIRDSFOOT TREFOIL	<u>8</u>	0.20
OTAL	48	1.10

- . SEEDBED PREPARATION


 A. SURFACE AND SEEPAGE WATER SHOULD BE DRAINED OR DIVERTED FROM THE SITE TO PREVENT DROWNING OR WINTER KILLING OF THE PLANTS.
- B. STONES LARGER THAN FOUR INCHES AND TRASH SHOULD BE REMOVED BECAUSE THEY INTERFERE WITH SEEDING AND FUTURE MAINTENANCE OF THE AREA. WHERE FEASIBLE, THE SOIL SHOULD BE TILLED TO A DEPTH OF ABOUT FOUR INCHES TO PREPARE A SEEDBED AND MIX FERTILIZER AND LIME INTO THE SOIL. THE SEEDBED SHOULD BE LEFT IN A REASONABLY FIRM AND SMOOTH CONDITION. THE LAST TILLAGE OPERATION SHOULD BE PERFORMED ACROSS THE SLOPE WHEREVER PRACTICAL.
- 2. ESTABLISHING A STAND

 A. LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF SEEDING AND INCORPORATED INTO THE
 SOLL KINDS AND AMOUNTS OF LIME AND FERTILIZER SHOULD BE BASED ON EVALUATION OF SOIL TESTS. WHEN
 A SOIL TEST IS NOT AVAILABLE, THE FOLLOWING MINIMUM AMOUNTS SHOULD BE APPLIED:

- AGRICULTURAL LIMESTONE: 2 TONS PER ACRE OR 0.09 LBS. PER SQ. FT.
 NITROGEN (N): 50 LBS. PER ACRE OR 1.1 LBS. PER 1000 SQ. FT.
 PHOSPHATE (P-0-): 100 LBS. PER ACRE OR 2.2 LBS. PER 1000 SQ. FT.
 POTASH (K-0-): 100 LBS. PER ACRE OR 2.2 LBS. PER 1000 SQ. FT.
 POTASH (K-0-): 100 LBS. PER ACRE OR 2.2 LBS. PER 1000 SQ. FT.
 (NOTE: THIS IS THE EQUIVALENT OF 500 LBS. PER ACRE OF 10–20–20 FERTILIZER OR 1,000 LBS. PER ACRE OF 5–10–10)
- B. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE. METHODS INCLUDE BROADCASTING, DRILLING, AND HYDROSEEDING. WHERE BROADCASTING IS USED, COVER SEED WITH 0.25 INCH OF SOIL OR LESS, BY OULTPACKING OR RAKING.
- C. REFER TO TABLE 7-35 OF "STORMWATER MANAGEMENT AND SEDIMENTATION CONTROL HANDBOOK FOR URBAN AND DEVELOPING AREAS IN NEW HAMPSHIRE", FOR APPROPRIATE SEED MIXTURES AND TABLE 7-36 FOR RATES OF SEEDING. ALL LEGUMES (CROWNVETCH, BIRDSFOOT TREFOIL, AND FLATPEA), MUST BE INOCULATED WITH THEIR SPECIFIC INNOCULANT.
- D. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY OCTOBER. WHEN SEEDED AREAS ARE NOT MULCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20 OR FROM AUGUST 10 TO SEPTEMBER 1.
- MULCH
 A. STRAW, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER SEEDING.
- B. MULCH WILL BE HELD IN PLACE USING TECHNIQUES FROM THE "BEST MANAGEMENT PRACTICE FOR MULCHING", AS SHOWN IN, "STORMWATER MANAGEMENT AND SEDIMENTATION CONTROL HANDBOOK FOR URBAN AND DEVELOPING AREAS IN NEW HAMPSHIRE".
- MAINTENANCE TO ESTABLISH A STAND
 PLANTED AREAS SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE WEED GROWTH.
- B. FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL FERTILIZER IS USUALLY THE KEY TO FULLY COMPLETE THE ESTABLISHMENT OF THE STAND BECAUSE MOST PERENNIALS TAKE 2 TO 3 YEARS TO BECOME ESTABLISHED.
- C. IN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED, OCCASIONAL MOWING MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VEGETATION.

TEMPORARY SEEDING RATES:

- FOR FALL SEEDING (SEED FROM AUGUST 15 SEPTEMBER 5 FOR BEST COVER): WINTER RYE: 2.5 LBS PER 1,000 SF SEED TO A DEPTH OF 1 INCH
- FOR SPRING SEEDING (SEED NO LATER THAN MAY 15 FOR SUMMER PROTECTION) OATS: 2 LBS PER 1,000 SF SEED TO A DEPTH OF 1 INCH
- ALTERNATIVE:
 PERENNIAL REYGRASS: 0.7 LBS PER 1,000 SF
 SEED BETWEEN APRIL 1 AND JUNE 1 AND/OR BETWEEN
 AUGUST 15 AND SEPTEMBER 15)
 MULCHING WILL ALLOW SEEDING THROUHGOUT THE GROWING SEASON.
 SEED TO A DEPTH OF 0.5 INCHES
- 10-10-10 FERTILIZER SHOULD BE UNIFORMERLY SPREAD OVER AREA PRIOR TO BE INCORPORATED INTO THE SOIL AT A MINIMUM OF 7 LBS PER 1,000 SF



- 1. STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 3 INCH STONE RECLAIMED STONE, OR RECYCLED CONCRETE EQUIVALENT.
- 2. THE LENGTH OF THE STABILIZED ENTRANCE SHALL BE NOT LESS THAN 50 FEET, EXCEPT FOR A SINGLE RESIDENTIAL LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY
- 3. THE THICKNESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6 INCHES.
- 4. THE WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN THE FULL WIDTH OF THE ENTRANCE WHERE INGRESS OR EGRESS OCCURS OR 10 FEET, WHICH EVER IS GREATER.
- 5. GEOTEXTILE FILTER CLOTH SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING THE STONE. FILTER CLOTH IS NOT REQUIRED FOR A SINGLE FAMILY RESIDENTIAL LOT.
- 6. ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL, A BERM WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE.
- 7. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OF FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OF CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, WASHED OR TRACKED ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED PROMPTLY.
- 8. WHEELS SHALL BE CLEANED TO REMOVE MUD PRIOR TO ENTRANCE ONTO PUBLIC RIGHTS-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.

STABILIZED CONSTRUCTION ENTRANCE / EXIT

EPA: NPDES GENERAL NOTES

- THE PROPOSED LAND DISTURBANCE IS APPROXIMATELY XXX,XXX SF., THEREFORE, ACCORDING TO THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PHASE II CONSTRUCTION GENERAL PERMIT (CGP) SECTION 1.1, THIS PROJECT IS NOT REQUIRED TO COMPLY WITH THE REGULATORY CRITERIA AND INTENT OF THE NPDES PHASE II PROGRAM, LATEST EDITION. SITE AREA DOES NOT EXCEED 43,560 SF (1 ACRE OF DISTURBANCE).
- THE OWNER AND CONTRACTOR ARE NOT REQUIRED TO PREPARE, MAINTAIN AND HAVE ON FILE A STORM WATER POLLUTION PREVENTION PLAN (SWPPP).
- THE OWNER AND CONTRACTOR ARE REQUIRED TO PREPARE, SUBMIT, POST ON SITE AND HAVE ON FILE A NOTICE OF INTENT (NOI). CONSTRUCTION <u>MAY NOT COMMENCE</u> UNTIL 14 DAYS AFTER EPA HAS REVIEWED/APPROVED THE PROJECT NOI, WHICH GRANTS COVERAGE UNDER THE COP (NHRTGODOD).
- THE CONTRACTOR/OWNER IS RESPONSIBLE TO POST THE NOI ON SITE IN A HIGHLY VISIBLE POSITION, PROTECTED FROM THE WEATHER.
- THE OWNER AND CONTRACTOR ARE REQUIRED TO INSTALL, INSPECT AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES AS DESCRIBED ON THE APPROVED PLANS AND SWPPP INCLUDING INSPECTION LOGS.
- THE OWNER OR CONTRACTOR MAY CONTACT THE NORTHEAST EPA REGIONAL COORDINATOR FOR RESOLUTION TO ANY NPDES, CGP, SWPPP, NOI OR NOTE QUESTIONS, CONCERNS OR CLARIFICATION:

EPA REGIONAL REPRESENTATIVE: MS. THELMA MURPHY (OR CURRENT REPRESENTATIVE) US EPA, REGION 01/OFFICE OF ECOSYSTEM PROTECTION 1 CONGRESS STREET, SUITE 1100 BOSTON, MA 02114-2023 PHONE: (617) 918-1615

- THE PROPOSED PROJECT WILL REQUIRE STATE (NHDES) ALTERATION OF TERRAIN PERMIT, SINCE THE ANTICIPATED LAND DISTURBANCE IS LESS THAN 100,000 SF, ACCORDING TO ENV-WS 415.
- THE PROPOSED PROJECT WILL REQUIRE A STATE (NHDES) DREDGE AND FILL PERMIT, SINCE THE PROJECT DOES NOT HAVE WETLAND DISTURBANCES. ACCORDING TO WT 302.04.

CONSTRUCTION SEQUENCE / EROSION CONTROL NOTES:

- THE PROJECT IS TO BE MANAGED IN A MANNER THAT MEETS THE REQUIREMENTS AND INTENT OF RSA 430:53 AND CHAPTER Agr 3800 RELATIVE TO INVASIVE SPECIES.

- 5. ALL DITCHES AND SWALES SHALL BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
- B. ALL EROSION CONTROLS SHALL BE INSPECTED WEEKLY AND AFTER EVERY HALF-INCH OF RAINFALL
- 9. LIMITS ON OPEN AREA ALLOWED, SEE Env-Wg 1505.02 FOR DETAILED INFORMATION

- 10. DEFINITION OF THE WORD STABLE:


 0. BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED.

 1. A MINIMUM OF 35 PERCENT VEGETATED GROWTH HAS BEEN ESTABLISHED.

 1. A MINIMUM OF 3 INCHES OF NON-ERGSIVE MATERIAL SUCH STONE OR RIPRAP HAS BEEN INSTALLED.

 1. OR, EROSION CONIROL BLANKETS HAVE BEEN PROPERLY INSTALLED.
- 11. ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE.

- 1. STRUCTURES SHALL BE INSTALLED ACCORDING TO THE DIMENSIONS SHOWN ON THE PLANS AT THE APPROPRIATE SPACING.
- 2. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER SO THAT EROSION WILL BE MINIMIZED,
- WHEN HAY BALES ARE USED, THEY ARE TO BE EMBEDDED INTO THE SOIL 4 INCHES.
 WHEN TIMBERS ARE TO BE USED, THE TIMBER SHALL EXTEND AT LEAST 18 INCHES INTO THE SOIL.
- HAY OR STRAW BALES SHALL BE ANCHORED INTO THE SOIL USING 2"x2" STAKES DRIVEN THROUGHOUT THE BALES AT LEAST 18 INCHES INTO THE SOIL.
- SEEDING, FERTILIZING AND MULCHING SHALL CONFORM TO THE RECOMMENDATIONS IN THE APPROPRIATE BMP.
- 6. STRUCTURES ARE TEMPORARY AND ARE TO BE REMOVED FROM THE CHANNEL WHEN THEIR USEFUL LIFE HAS EXPIRED, WHEN A SOLID STAND OF GRASS HAS CONSIDERABLE OF THE STAND OF GRASS HAS CONSIDERABLE OF THE STAND OF THE STAND



TEMPORARY STONE CHECK DAM

NOT TO SCALE

NO SCALE

N.H. LAND Consultants SURVERING-LAND PLANNING- REAL ESTATE

叫得

LLC. EROSION CONTROL NOTES
TAX MAP 6 LOT 16
APPLICANT / OWNER:
DVENTURE CAMPER RENTALS, L.
BRETT AND AMY TKACZYK
O MILL POND ROAD, NORTHWOOD NH 035

ð 30

JOB NO: 592.00 ROCKINGHAM CO. DATE: APRIL 18, 2022

DET-5